

COPPER CATEGORY 6A F/FTP CABLING SYSTEM Giganet Pre-Terminated Category 6A Trunking

The GIGANET copper pre-terminated CAT 6A F/FTP shielded copper trunk assemblies provide cost effective high performance for Data Centers and quick network deployment between telecommunication racks .Factory termination are T568B and testing ensures guaranteed performance compared to field terminated installation saving time and labor .The GIGANET copper trunk assemblies are available in various lengths and a choice of 6 or 12 cable bundle using LSOH jacket.

| CABLE CHARACTERISTICS | | |
|---|--|--|
| 6 or 12 legged cable bundles LSOH cable jacket | | |
| Factory terminated and tested | | |
| Rapid Deployment | | |
| High Performance and Reliability | | |
| Assemblies made to length | | |
| Direct Connection to Equipment/Panel | | |
| Custom made to order | | |
| Fast and easy installation with reduced labor costs | | |
| Pulling eye to ease Installation | | |
| Qualified for PoE and PoE+ IEEE 802.3at. | | |
| Pre-terminated assemblies are eligible for GIGANET warranty | | |
| Flame Resistant | | |
| 0.57mm / 23 AWG solid Plain Copper | | |
| All pairs shielded with Drain Wire | | |





| PRODUCT INFORMATION | |
|------------------------------|---|
| Part Number | Product Description |
| GN-C6A-F/FTP-LSOH-CTA-06L-XX | Giganet Category 6A 6 Leg F/FTP LSOH Trunking Assemblies |
| GN-C6A-F/FTP-LSOH-CTA-12L-XX | Giganet Category 6A 12 Leg F/FTP LSOH Trunking Assemblies |

where

XX = Cable length in Meters (2-72)

